

Notice of Requirement Draft Conditions

1. A detailed plan showing all landscape planting associated with the Edendale State highway 1 realignment is to be submitted to Council's Manager Resource Management for certification prior to construction works commencing.
2. An Earthworks Management Plan shall be submitted to Council's Manager Resource Management for certification prior to earthworks commencing.
3. The contractor will undertake dust suppression as necessary during the construction period in order to mitigate potential dust effects in dry conditions.
4. Machinery shall generally operate only during normal daylight hours and contractors will comply with NZS 6803: 1999 'Acoustics - Construction Noise'.
5. Construction Noise Management Plan

A Construction Noise Management Plan is to be prepared and submitted to Council's Manager Resource Management for certification prior to construction works commencing. The Noise Management Plan shall include:

- a. Description of the works, anticipated equipment processes/durations;
- b. Identification of the noise-sensitive receivers likely most affected by construction noise of specific construction activities;
- c. "Construction noise upper limits" determined with regard to the receiving noise environment and including daily/weekly scheduling considerations, and with regard to any specific consent/designation requirements, and this may also take into account where particular noise-sensitive receivers are recently subject to other construction noise sources;
- d. Assessment of likely construction noise levels and scheduling, with appropriate noise mitigation measures to be implemented;
- e. Establishing a monitoring regime which targets both the more noisy activities and their potential occurrences near noise-sensitive locations;

- f. Staff training/awareness programme;
- g. Procedures for maintaining contact with stakeholders, including informing them when noisy activities may occur and providing summary reports of monitoring and investigations of any noise complaints;
- h. Process for managing noise complaints; and
- i. Contact telephone numbers for key construction staff, staff responsible for noise assessment and Council offices, plus a single point of contact for immediate advice of concerns about noisy activities.

6. Archaeological Discovery Condition

The contractor is to stop work immediately and comply with the requirements of the Historic Places Act 1993 if there are any discoveries of unrecorded archaeological or cultural material during the course of construction works.

7. Kōiwi Accidental Discovery

If Kōiwi (human skeletal remains) are discovered, then work shall stop immediately and Te Ao Mārama Incorporated (Ngāi Tahu (Murihiku) Resource Management Consultants) will be advised.

They will arrange a site inspection by the appropriate tangata whenua and their advisers, including statutory agencies, who will determine whether the discovery is likely to be extensive and whether a thorough site investigation is required.

In recognition of Section 6 of the Resource Management Act 1991 and legal requirements under the Historic Places Act 1993, there is a requirement to consult Heritage New Zealand when archaeological sites are disturbed without authorisation previously obtained. The New Zealand Police also need to be consulted if the discovery includes Kōiwi or human remains.

Materials discovered will be handled and removed by Iwi responsible for the tikanga appropriate to their removal or preservation.

Taonga or Artefact Accidental Discovery

Taonga or artefact material (e.g. pounamu/greenstone artefacts) other than Kōiwi will be treated in a similar manner so that their importance can be determined and the environment recorded by qualified archaeologists alongside the appropriate tangata whenua.

In-situ (Natural State) Pounamu/Greenstone Accidental Discovery

Pursuant to the Ngāi Tahu (Pounamu Vesting) Act 1997, all natural state pounamu/greenstone in the Ngāi Tahu tribal area is owned by Te Rūnanga o Ngāi Tahu. The Ngāi Tahu Pounamu Resource Management Plan provides for the following measures:

- Any *in-situ* (natural state) pounamu/greenstone accidentally discovered should be reported to the Pounamu Management Officer of Te Rūnanga o Ngāi Tahu as soon as is reasonably practicable. The Pounamu Management Officer of Te Rūnanga o Ngāi Tahu will in turn contact the appropriate Kaitiaki Papatipu Rūnanga.
- In the event that the finder considers the pounamu is at immediate risk of loss such as erosion, animal damage to the site or theft, the pounamu/greenstone should be carefully covered over and/or relocated to the nearest safe ground. The find should then be notified immediately to the Pounamu Management Officer.

Contact details for the Pounamu Management Officer are as follows:

Te Rūnanga o Ngāi Tahu

E-mail: info@ngaitahu.iwi.nz

50 Corsair Drive

Tel: +64 3 366 4344

PO Box 13046

Tel: 0800 KAI TAHU (0800 524 8248)

Wigram

Fax: +64 3 341 6792

Christchurch 8141